



Policy:	Site Impact Policy	Reference:	SISES0030
		Review Date:	05/2023

Purpose.

To ensure a general state of cleanliness and tidiness of the workplace, and to prevent any adverse effects or conflicts with the existing environment.

Scope.

- Site access and traffic routes.
- Maintenance of facilities.
- Removal of rubbish from work areas and storage of waste materials.

Responsibilities.

The Site Manager, through his line management will be responsible for ensuring the above are adequately controlled.

Site Access and Traffic Routes.

- All access ways and traffic routes shall be directed such that impact on the existing environment is minimised. This can be achieved by ensuring suitable routes and times for site deliveries are planned in advance. By staggering shift schedules to ensure that a sudden influx of traffic does not cause unnecessary adverse impact, making sure that nuisance to local communities is reduced to a minimum.
- No access way or traffic route shall conflict with any area of Nature Conservation or Site of Special Scientific Interest. Such sites shall remain undisturbed.

Maintenance of Facilities.

- All site facilities as far as possible shall be situated and maintained so as not to clash with the existing environment and planning consent.
- Any temporary buildings or cabins shall be configured in such a manner to have minimum impact within their surroundings. All site facilities shall be kept in a manner that does not give rise to vermin infestation. Security measures will be taken in order to maintain the integrity of stored substances and waste from vandalism.

Removal of Rubbish from Work Areas and Storage of Waste Materials.

- All waste will be removed from work areas daily and placed into segregated waste storage pending removal by licensed waste contractor.
- All waste storage will be suitable for task and will prevent any contamination leaching into watercourses, drains or land.
- Storage areas will be maintained in a tidy condition and wastes removed at regular intervals to prevent a build-up.